


February 24 – February 28, 2013 ♦ Phoenix, Arizona

Future Vision: The West Valley Demonstration Project 2020

Craig R. Rieman
U.S. Department of Energy
West Valley Demonstration Project

WVDP Site Facilities









The West Valley Demonstration Project









WVDP Mission

The WVDP mission was defined by an act of Congress in 1980 – Public Law 98-368

Solidify the high-level radioactive waste at the Center

Completed

- 99.7% of the curies in the tanks were vitrified and the glass is contained in 275 stainless steel canisters
- Develop containers suitable for permanent disposal of the waste

Completed

 Transport the solidified waste to a federal repository for permanent disposal

Pending Repository

Dispose of low-level radioactive waste and transuranic waste

In Progress

 Decontaminate and decommission the underground high-level waste tanks, facilities and any material and hardware used in connection with the Project

In Progress






WVDP Accomplishments/Successes

Commercial reprocessing plant sitting idle—WVDP Act signed into law in 1980

Retrofit Const.

Processed, packaged, stored TRU waste on site

Processed, packaged, shipped LLW to offsite disposal



2 of 5 WVDP Act mandates fulfilled





Phased Decisionmaking

In 2010, DOE published the Final Environmental Impact Statement and Record of Decision (ROD) for Decommissioning and/or Long-Term Stewardship at the West Valley Demonstration Project and the Western New York Nuclear Service Center

- Phased Decisionmaking ROD
- Phase 1 Decommissioning Plan

Phase 1 Studies

- Final Decommissioning ROD
- Phase 2 Decommissioning Plan

Phase 1 Decommissioning

Phase 1 Facility Disposition

- Relocate 275 HLW Canisters to new dry cask storage facility
- Demolish Vitrification Facility (Vit) and Main Plant Process Building (MPPB)
 - Remove ancillary facilities
- Ship legacy Low Level Waste

Phase 1 Soil Remediation

- Remove Below Grade Portion of MPPB and Vit (including source area of plume)
- Remove Lagoons and Liquid Waste Treatment Facility
- Ship Legacy TRU Waste
- Remove Remote Handled Waste Facility and remaining ancillary facilities
- Remediate all WMA 1 & 2 Soil

Phase 2 Decommissioning

(Decisions made by 2020)

Phase 2 Decisions

- Closure decision for Waste Tank Farm
- Closure decisions for NRC-licensed Disposal Area and State-licensed Disposal Area





safety & performance & cleanup & closure



WVDP Decommissioning Timeline

Processed, packaged, stored TRU waste on site

Processed, packaged, shipped LLW to offsite disposal

Final D&D

2010 2011 2012 2013 2014 2015 2016 2017 2018 2019 2020

Phase 1 Facility Disposition*

Demolish 01-14 Facility

- Relocate 275 HLW canisters
- Remove above grade portions of MPPB & Vitrification facility
- Demolish ancillary facilities
- Package TRU waste for disposal; store on site
- Manage HLW & TRU on-site
- Dispose LLW

Published Record

Decommissioning

of Decision for

Phase 1

*Based on \$75M/yr funding

Phase 1 Soil Remediation

Remove:

- Below grade portions of MPPB and Vit, including plume source
- RHWF
- Lagoon 1
- Demineralizer sludge ponds and LLWTF

Manage HLW on-site Dispose LLW & TRU

Publish Record of Decision for Phase 2 decommissioning

Phase 2 Decommissioning

- Implement decisions for:
- HLW canisters
- Waste tank farm
- NRC-licensed disposal area
- State-licensed disposal area

Manage HLW on-site Dispose LLW


Phase 1 Studies





Challenge: HLW Disposal

- Relocating waste from Main Plant's High Level Waste Interim Storage to a stand alone dry cask storage system:
 - 275 HLW canisters
 - 2 evacuated canisters
 - 1 non-routine HLW canister
 - 2 SNF debris drums
- Use current licensed SNF shipping cask multi-purpose canister overpacks and current SNF cask designs:
 - 5 HLW canisters per package
 - 3 canisters in separate cask
 (2 evacuated canisters and 1 non-routine canister)
 - SNF debris in separate cask








HLW Disposal continued

- Packaging non-conforming HLW is problematic
 - Currently evaluating Waste
 Acceptance Product Specifications
 (WAPS) for Vitrified High-Level Waste
 Forms DOE/EM-0093 Rev 3
 - Pursuing alternatives for SNF debris
- HLW interim storage will be provided on site until a federal repository for permanent disposal is available







Major Challenges for Decommissioning

The WVDP faces challenges for Decommissioning:

- Disposal of transuranic waste (TRU)
- Disposal of high-level waste (HLW)
- Disposition of underground tanks that contained HLW
- Disposition of shallow land burial grounds
- Sufficient funding to enable steady progress
 - Funding reductions = increased risk



Main Plant Process Building & associated facilities





Challenge: TRU disposal continued

- WV Managing ~ 1,200 m³ of TRU/GTCC RH, CH, Mixed, Non-Mixed
- Most TRU/GTCC by WIR, contains fuel debris or is contaminated with TRU material originating from Head End or Vitrification processes
- High dose rate RH-TRU
- Prolonged storage of TRU will slow decommissioning progress, i.e. need to maintain storage facilities





Challenge: TRU Disposal



The Horizontal Emplacement and Retrieval Equipment (HERE) is used to push remote-handled transuranic waste into horizontal boreholes in the disposal room walls.





Challenge: Disposition of In-Ground Facilities

Underground tanks

- DOE desires consistent approach complex-wide
 - Performance modeling
 - Decommissioning/closure methodology
- RCRA regulation of WVDP vs CERCLA at other sites
- West Valley site subject to NRC decommissioning requirements


Shallow land burial ground


- Does not meet NRC requirements in its current condition
- West Valley site subject to NRC decommissioning requirements





Challenge for WVDP Completion: Funding





Funding priorities

- ~\$20M/yr for min safe operations
- HLW canister relocation (critical path)

Impacts of reduced funding

- Delays scheduled activities
 - Waste shipments
 - Demolition of facilities
- Increases costs
 - Upgrades/maintenance of waste storage facilities
 - Continued monitoring & maintenance of waste in storage
 - Continued monitoring & maintenance of facilities slated for demolition



The WVDP Vision for 2020

