

ICP

IDAHO CLEANUP PROJECT

Infamous Pit 9 Era Comes to a Close

Presented by
Jim Malmo, US DOE-ID and Hoss Brown, CH2M-WG Idaho

February 2013




SAFELY PLAN • MOTIVATE • DELIVER

Background




- ◆ **Demonstration project – Glovebox Excavator Method (GEM) (2004)**
 - Remediation of small portion of Pit 9
 - ◆ Constructed enclosure structure over pit
 - ◆ Isolated backhoe for excavation



Glovebox Excavator Method (GEM)



Background (continued)



ICP-I Challenges (post May 2005)

- ◆ **Ensuring proper balance of available equipment and equipment reliability in order to maintain continuous operations**
- ◆ **Anticipating production impacts such as**
 - Pyrophoric events caused by drums containing roaster oxides
 - Subsidence issues with waste retrieval enclosures
 - Potential for degraded drums
- ◆ **Developing construction/exhumation sequencing to achieve optimal schedule execution**



Driver prepares to enter retrieval area

Safety Excellence = Safe Production



- ◆ More than 7,500 entries into radiological/contamination areas without an event
- ◆ No recordable injuries



Radiological control technician assists ARP worker prior to entering high radiation area

Planning




- ◆ **Optimized sequencing of GEM decontamination/decommissioning/demolition with ARP V design/construction – ensuring exhumation facility was ready when operations crew was available**
- ◆ **Produced exhumation facility design that utilized**
 - Existing Pit 9 concrete foundation – saving DOE the cost of constructing a new foundation
 - Worker involvement and feedback for optimum constructability



Sustainable Production



- ◆ Invested in appropriate equipment and maintenance capabilities, avoiding production delays due to equipment failure
- ◆ Designed, constructed, and operated a fissile material measurement system that reduced the generation of orphan waste – from as high as 12% to less than .02%
- ◆ Designed ARP V as a “stand alone” facility, independent of the other four (ARPs) interconnected facilities



Buried
waste
exhumation
in Pit 9

Innovations/Process Improvements



- ◆ **Instituted procedure modifications to address pyrophoric reactions**
 - Analyzed/anticipated/proceduralized recovery action
 - Resulted in little to no impact to production or risk to operators
- ◆ **Consolidated all key project functions at the job site**
- ◆ **Used existing concrete foundation**
- ◆ **Encased existing firewater supply line in concrete**
 - Avoided relocation costs
 - Protected it from exhumation operations
- ◆ **Applied Integrated Safety Management System (ISMS) principles, specifically worker feedback, to achieve operational/construction improvements**

Outcomes



- ◆ **In August 2011, completed the targeted waste exhumation of Pit 9**
 - One year ahead of schedule
 - \$10 million under budget
 - No recordable injuries; no radiological events
- ◆ **Achieved regulatory end-state for one of the most politically charged DOE projects at the Idaho Site**
- ◆ **Reuse of Pit 9 facility for processing of 6,000 AMWTP sludge drums**
 - Exceeded the facility from CERCLA
 - Received RCRA permit for sludge repackaging

Successful Pit 9 team

