

Overview of Hanford Single Shell Tank (SST) Structural Integrity - 14203

Rick Rast, P.E.
Washington River Protection Solutions, WRPS
P.O. Box 850 MSIN
Richland, WA 99352-58
Richard_S_Rast@rl.gov
(509)-376-6056

D.J. Washenfelter, WRPS
J. M. Johnson, USDOE/ORP

ABSTRACT

To improve the understanding of the single-shell tanks (SSTs) integrity, Washington River Protection Solutions, LLC (WRPS), the USDOE Hanford Site tank contractor, developed an enhanced Single-Shell Tank Integrity Project (SSTIP) in 2009. An expert panel on SST integrity, consisting of various subject matters experts in industry and academia, was created to provide recommendations supporting the development of the project. This panel developed 33 recommendations in four main areas of interest: structural integrity, liner degradation, leak integrity and prevention, and mitigation of contamination migration. Seventeen of these recommendations were used to develop the basis for the M-45-10-1 Change Package for the Hanford Federal Agreement and Compliance Order, which is also known as the Tri-Party Agreement.

The structural integrity of the tanks is a key element in completing the cleanup mission at the Hanford Site. There are eight primary recommendations related to the structural integrity of Hanford Single-Shell Tanks. Six recommendations are being implemented through current and planned activities. The structural integrity of the Hanford is being evaluated through analysis, monitoring, inspection, materials testing, and construction document review.

Structural evaluation in the form of analysis is performed using modern finite element models generated in ANSYS. The analyses consider in-situ, thermal, operating loads and natural phenomena such as earthquakes. Structural analysis of 108 of 149 Hanford Single-Shell Tanks has concluded that the tanks are structurally sound and meet current industry standards. Analysis of the remaining Hanford Single-Shell Tanks is scheduled for FY2014.

Hanford Single-Shell Tanks are monitored through a dome deflection program. The program looks for deflections of the tank dome greater than 1/4 inch. No such deflections have been recorded. The tanks are also subjected to visual inspection. Digital cameras record the interior surface of the concrete tanks, looking for cracks and other surface conditions that may indicate signs of structural distress.

The condition of the concrete and rebar of the Hanford Single-Shell Tanks is currently being tested and planned for additional activities in the near future. Concrete and rebar removed from the dome of a 65 year old tank was tested for mechanics properties and condition. Results indicated stronger than designed concrete with additional Petrographic examination and rebar

completed. Material properties determined from previous efforts combined with current testing and construction document review will help to generate a database that will provide indication of Hanford Single-Shell Tank structural integrity.

INTRODUCTION

The Hanford Single-Shell Tank Integrity Project (SSTIP) was developed as a means to implement Single-Shell Tank Integrity Expert Panel (Panel) recommendations related to structural integrity, leak integrity, leak identification and prevention, and mitigation of contaminant migration [1]. The structural integrity of Hanford Single-Shell Tanks (SSTs) is not a current concern, but is a sensitive topic that spans decades back before Hanford Double-Shell Tanks (DSTs) were constructed. The large number (count = 149) of SSTs and varying operating histories places a great deal of emphasis on the unknowns associated with these buried reinforced concrete structures. The SSTIP activities implementing Panel recommendations look to develop a better understanding of the structural integrity of Hanford SSTs.

SST STRUCTURES

Hanford Single-Shell Tanks are either 20-ft diameter (200-series, count = 16) or 75-ft diameter (100-series, count = 133) reinforced concrete structures, buried underground on the Hanford Site. The SSTs are typically recognized by their alphanumeric identifier containing the facility designation, farm name, and tank number.




For example: 241-A-106




Where:

- 241 is the facility designation for Waste Storage Tank (WST)
- A is the identifier A-farm
- 106 is the number, identifying it as 100-series, or 75-ft diameter SST

From a structural perspective, the SSTs are broken down into tank types, relating to the age and design of the structures. There are 4 types of SSTs and 3 subtypes of the Type IV SSTs. The Type I tanks reflect the original design of the SSTs. Production facilities generated more waste than originally anticipated and required more disposal capacity than the Type I tanks could afford. This led to the construction of the 75-ft diameter Type II tanks. The 75-ft diameter size was not changed after that. Increased need for storage after that led to the construction of more, taller tanks (Type III and IV SSTs). Table I provides descriptions of the SST structures.

TABLE I. Single-Shell Tank Structure Details

	<p>Type I Single-Shell Tank:</p> <ul style="list-style-type: none"> • Diameter = 20-ft • Height = 25-ft 7-in • Wall Thickness = 12-in • Footing Thickness = 18-in • Concrete design strength = 3000-psi • Rebar yield strength = 40,000-psi • Capacity = 55-kgal
	<p>Type II Single-Shell Tank:</p> <ul style="list-style-type: none"> • Diameter = 75-ft • Wall Height = 21-ft • Wall Thickness = 12-in • Dome Height = 8-ft 8-in • Dome Thickness = 15-in • Footing Thickness = 24-in • Concrete design strength = 3000-psi • Rebar yield strength = 40,000-psi • Capacity = 530-kgal
	<p>Type III Single-Shell Tank:</p> <ul style="list-style-type: none"> • Diameter = 75-ft • Wall Height = 27-ft • Wall Thickness = 15-in • Dome Height = 8-ft 8-in • Dome Thickness = 15-in • Footing Thickness = 24-in • Concrete design strength = 3000-psi • Rebar yield strength = 40,000-psi • Capacity = 758-kgal

	<p>Type IVa Single-Shell Tank:</p> <ul style="list-style-type: none"> • Diameter = 75-ft • Wall Height = 35-ft 8-in • Upper Wall Thickness = 15-in • Lower Wall Thickness = 24-in • Dome Height = 8-ft 9-in • Dome Thickness = 15-in • Footing Thickness = 23-in • Concrete design strength = 3000-psi • Rebar yield strength = 40,000-psi • Capacity = 1000-kgal
	<p>Type IVb Single-Shell Tank:</p> <ul style="list-style-type: none"> • Diameter = 75-ft • Wall Height = 37-ft • Upper Wall Thickness = 15-in • Lower Wall Thickness = 24-in • Dome Height = 8-ft 9-in • Dome Thickness = 15-in • Footing Thickness = 24-in • Concrete design strength = 3000-psi • Rebar yield strength = 40,000-psi • Capacity = 1000-kgal
	<p>Type IVc Single-Shell Tank:</p> <ul style="list-style-type: none"> • Diameter = 75-ft • Wall Height = 38-ft • Upper Wall Thickness = 15-in • Lower Wall Thickness = 24-in • Dome Height = 6-ft 9-in • Dome Thickness = 15-in • Footing Thickness = 36-in • Concrete design strength = 4000-psi • Rebar yield strength = 40,000-psi • Capacity = 1000-kgal

STRUCTURAL INTEGRITY RECOMMENDATIONS

The Single-Shell Tank Integrity Expert Panel presented the Tank Operations Contractor (TOC) with a series of recommendations to develop an enhanced Single-Shell Tank Integrity Project. Eight of the Panel recommendations focused on structural integrity. The Panel prioritized their recommendations, SI-1 as most important.

The following is a list each of the original structural integrity recommendations and provides a brief description of the intent.

- **Recommendation SI-1, Perform Modern Structural Analyses:** The Panel recommends performing modern structural analyses (including seismic) on representative samples of SSTs. Such analyses are necessary to understand the structural integrity of the SSTs during a seismic event. The analysis will be useful in answering the following questions: How much rebar must remain to achieve adequate structural integrity under a major seismic event? What is the level of confidence that at least this amount of rebar cross-sectional area exists and will remain present for the operating life of the tanks (e.g., 20 to 50 additional years)? What is the minimum required concrete strength?
- **Recommendation SI-2, Perform Dome Deflection Surveys:** The Panel recommends continuation of the current dome deflection survey program. The program should be augmented to obtain dome deflection data near the haunch of the domes. The dome surveys are important as any future potential for dome collapse would be preceded by excessive downward dome deflection. The haunch data is important to determine whether dome deflections are due to downward displacement of the dome or of the footing under the sidewall.
- **Recommendation SI-3, Obtain and Test Sidewall Core:** The Panel recommends obtaining and testing a vertical core from the entire depth of the sidewalls for two tanks that have leaked and had been operated at high temperatures for extended periods. Such cores will provide important data about the structural condition of concrete and rebar in the sidewalls.
- **Recommendation SI-4, Perform Non-Destructive Evaluation of Concrete:** The Panel emphasizes the importance of the hierarchical aspect of this recommendation. Initially, the Panel recommends the application of two technologies: (1) visual inspection of domes to identify cracks in excess of 1/16 inch wide, rust stains on the concrete, or spalling of concrete, and (2) utilization of a ‘thumper’ truck to determine the modulus of the dome concrete. The modulus correlates with concrete strength and controls the degree of deformation that will occur under loading. Additional NDE methods will be implemented in conjunction with recommendation SI-3.
- **Recommendation SI-5, Test Dome Concrete and Rebar ‘Plugs’:** Current plans call for the cutting of holes in the SST domes to facilitate the use of retrieval equipment. The Panel recommends the following tests on concrete and rebar ‘plugs’ removed from domes during cutting: (1) concrete compression and bend tests; and (2) rebar diameter

measurement and tensile tests. These tests will provide an opportunity to obtain data on the condition of the dome concrete and rebar.

- **Recommendation SI-6, Develop Engineering Mechanics Document:** The Panel recommends the development and up-to-date maintenance of a living document containing the best current understanding of engineering mechanics properties of each tank. Such a document is an important reference in understanding both the current and future structural integrity of the SSTs and will be useful in defining input information for future tank evaluations.
- **Recommendation SI-7, Test Effects of Waste Exposure on Structural Integrity:** The Panel recommends measuring the physical and mechanical properties of concrete exposed for more than 28 days to simulated waste. Based on these measurements, the effects of waste/concrete/rebar reactions and temperature on the structural integrity of the tank walls should be estimated. These tests will assist in determining whether liquid waste that has leaked through the steel liner and the concrete walls could have damaged the concrete and rebar.
- **Recommendation SI-8, Study the Deployment of Corrosion Potential Mapping:** The Panel recommends studying the feasibility of performing corrosion potential measurements to assess the condition of rebar in the SSTs. If potential mapping can be successfully deployed, it has the potential to detect active corrosion.

STRUCTURAL INTEGRITY IMPLEMENTATION

The Tank Operations Contractor, Washington River Protection Solutions (WRPS) programmatically reviewed the eight structural integrity recommendations in consultation with the U.S. Department of Energy (DOE). It was decided that all but two structural integrity recommendations would be implemented into the SSTIP.

The two recommendations were not selected partly because of lack of tank access, and partly because WRPS wanted to provide sufficient resources to the recommendations that would be implemented. The basis provided for not implementing SI-7 and SI-8 is as follows:

- **Recommendation SI-7, Test Effects of Waste Exposure on Structural Integrity:** This recommendation is not being pursued at this time. The data collected previously is deemed adequate in conjunction with the work being done to collect a core sample from 241-A-106. The data from this core along with data from 241-SX-108 and 241-SX-115 will provide a basis for estimated concrete properties.
- **Recommendation SI-8, Study the Deployment of Corrosion Potential Mapping:** This recommendation is not being pursued at this time. To deploy this system would require additional development. If the concrete integrity has been maintained, the rebar will not degrade. Should concrete degradation be identified as a potential risk, then work on rebar integrity would be pursued.

STRUCTURAL INTEGRITY ACTIVITIES

SI-1, Perform Modern Structural Analyses

WRPS subcontracted Pacific Northwest National Laboratories to perform the SST Analysis of Record (AOR). The AOR is being performed in a two phase approach. The initial phase consists of researching construction and operating histories, performing preliminary analysis to understand the extent of analysis to be performed, and developing structural evaluation criteria based on requested information, consensus standards, and required analytical methods. A second phase consists of performing detailed finite element modeling and analysis for each SST type. A report is to be generated per tank type, providing insight into the structural integrity of the SSTs based on known or assumed conditions. Figure 1 displays a 180 degree view of an SST finite element model that is used to perform the AOR. The view in Figure 1 shows different colored layers (or sections) of finite elements utilized in performing structural analysis.




Figure 1. SST Finite Element Model

The modern finite element analyses consider the effects of dead, live, thermal, and operating loads, in addition to natural phenomena hazards including earthquakes. The SST AORs include additional performance indicators such as limit load analyses and tank dome and wall buckling analyses [2]. The SST AORs also evaluate the effects of dome penetrations appurtenances, such as large concrete boxes or pits above the dome. The analytical models include the reinforced concrete SST structures and the surrounding soil. A matrix of concrete, soil, and waste configurations was utilized. Each AOR report is peer review by recognized industry experts. To date, the AORs have been completed for the Type II [3] and Type III [4] SSTs. Peer reviewers of the Type II and III analyses have agreed with the results and conclusions that based on the assumed condition of the concrete, the tanks are structurally sound. The analysis of the Type IV SSTs that is currently under development includes the consideration of proximity of adjacent tanks. The effects of Tank to Tank Interaction are required to be considered for four tanks on the Hanford Site. Type IVc SSTs, located in 241-AX farm are spaced at distances of 90-ft and 102-ft spacing in East-West and North-South Directions, respectively. Figure 2 shows the centerline

spacing for the Type IVc tanks. The wall spacing for the tanks is 131 inches in one the East-West direction and 275 inches in the North-South direction.




Figure 2. Type IVc SST Centerline Spacing

The Tank to Tank interaction analysis will provide details regarding the change in stress levels resulting from the thermal and seismic loading with respect to the tank proximity. The AOR, coupled with results from other implemented structural integrity recommendations will provide a basis for determination of SST structural integrity.

SI-2, Perform Dome Deflection Surveys

The existing SST dome surveys are conducted per the SST Dome Survey Program [5]. The program requires that all SSTs will be evaluated on a 24 or 36 month cycle, depending on the level of construction activity taking place in the SST farm. Action is required if a deflection in excess of 0.02 foot (0.24 inch) is identified.

Recent evaluation of the dome survey program identified some deficiencies that have been identified. As a result, engineering has prepared a benchmark matrix which specifically identifies the benchmark deficiencies and required repairs. This work is in progress. WRPS has completed all monument installations, benchmark (riser and pit tab) installations for 241-A, AX, C, B, and BY farms. Benchmark installations are scheduled to be completed in FY2013-14 for 241-SX, S, U and TX farms.

Current dome survey protocols reflect implementation of the Panel recommendation. Benchmark and survey monument protection and installation of new benchmarks have increased ability to detect true dome deflection in the dome elevation surveys. Dome deflection can be determined by subtracting the elevation at the center of the dome from the elevation at the perimeter of the tank. Settlement of the tank can be determined by subtracting the most current elevation at the perimeter of the tank from the first, or oldest, survey elevation at the perimeter of the tank. Current results indicate the tank settlement and dome deflection do not exceed the established criterion of 0.02-ft (0.24-in)

The results of the SST dome surveys are complemented by the limit state analyses provided in Analysis of Record (AOR) and other structural calculation documents. The deflections of the SST domes are far less than what is expected for dome collapse. The results from visual inspection of the inside of SSTs confirm the structural integrity of the domes. Additionally, concrete and rebar testing provide further evidence that the SST domes are structurally sound.

The survey data for the 100-series SSTs dates back to the late 1970s and early 1980s. The early survey data combined with results obtained under the current dome survey program provide excellent data for trending purposes as well. A compilation of SST dome survey data is provided in a detailed report [9]. An example of plotted survey data from 241-SX farm (15 tanks) is provided in Figure 3. The plot shows the change in elevation (in inches) with respect to the original elevation recorded for a given dome survey benchmark. The plotted data is from color coordinated per tank in the farm. Each data series represents a benchmark on the tank dome.




Figure 3. SST SX Farm Dome Survey

SI-3, Obtain and Test Sidewall Core

WRPS technical staff has identified 241-A-106 as the next SST that will be sidewall cored [6]. Although 241-A-106 is a sound tank, it was selected because it has the highest thermal operating history of the SSTs. Because concrete degradation is linked with high thermal operation, 241-A-106 should provide a bounding case for sidewall coring that meets the intent of the Panel's recommendation. Figure 4 shows a brief segment of the thermal history of SST 241-A-106, showing peak temperature of 594° F and 80+ month duration over 300° F.




Figure 4. SST 241-A-106 Thermal Profile

The goal of the SST Sidewall Coring activity is to remove intact cores for the entire depth of the sidewall, and half of the footing. The cores will be transported to a qualified testing laboratory and undergo mechanic testing and Petrographic examination similar to the 241-C-107 Cores mentioned further in this paper. This activity is planned to be performed from above the ground surface. The sidewall coring activity will require excavation down to the top of the tank wall, placement of a caisson, securing a guide tube to the tank, and mobilization of the drill rig and associated cooling water recirculation system. Figure 5 shows the planned configuration for sidewall coring.




Figure 5. A-106 (Type IVb) SST Sidewall Coring Schematic

To accomplish this, WRPS has hired Energy Solutions to perform SST sidewall coring. Criteria were developed such that the coring activity would not adversely affect the leak or structural integrity. A 4-in core barrel was selected and a 2-in clearance was identified, to keep the core barrel away from the horizontal wall rebar. Figure 6 shows a section of SST 241-A-106, with the 4-in diameter core barrel superimposed, highlighting the clearance.




Figure 6. SST Sidewall Coring Wall Cross-Section

The intent of the coring demonstration is to core a reinforced concrete wall, having similar construction characteristics to the Type IVB SST tank sidewalls intended to be cored during Phase 2. The key objective is to prove (by demonstration) that vertical core requirements can be obtained and maintained. The objectives of the concrete coring demonstration are as follows:

- Demonstrate that the coring method and tooling can successfully core and retrieve concrete samples;
- Demonstrate how the prefabricated alignment base serves as a starter for installing the guide casing and support the ability to control vertical axis deviation;
- Demonstrate that the core hole Z axis depth readings can be accurately measured;

- Demonstrate the X-Y axes verticality of the cored hole can be maintained within calculated tolerances to prevent the bit from breaking out through the concrete wall or cutting of horizontal hoop rebar;
- Demonstrate that the coring fluid circulation system provides for adequate hole cleaning; and
- Demonstrate that the coring fluid can be controlled, contained, and with minimal waste volume produced.

All demonstration objectives were met. The selected coring method proved to be extremely successful in retrieving intact core suitable for strength testing and was able to achieve and maintain vertical alignment within the required deviation tolerances. The maximum allowable vertical angle of deviation as specified in the Plan is 0 degrees, 10 minutes, 25 seconds (0°, 10', 25"). The calculation for this angle is based on a completed core hole with a depth of approximately 55 ft from ground surface (~ 38 ft of SST concrete wall and 17 ft of guide tubing) and a maximum allowable horizontal deviation of 2 in. at total depth. For the demonstration, a total of 33.31 ft of concrete was cored and recovered. The final depth of the core hole measured from the top of diverter was 38.6 ft (includes 5.29 ft of guide tubing). The final vertical angle of deviation was 0 degrees, 3 minutes, 41 seconds (0°, 03', 41"), with a final horizontal deviation measured at approximately 0.42 in. Extrapolating the measured angle of deviation to a 55 ft deep core hole, the horizontal deviation would measure 0.707 in. Both the vertical angle of deviation and the horizontal deviation of the demonstration core hole are well within the limits specified by the plan, RPP-PLAN-47370. The verticality surveying method was implemented effectively and equipment proved to be easy to operate and successfully demonstrated the ability to accurately measure and verify verticality of the core hole.

The initial design of the drilling fluid circulating system did not perform as expected and had to be modified to achieve the desired controls. The reconfiguration of the circulating system resulted in full containment and control of the circulating fluid and allowed for excellent hole cleaning.

The demonstration is considered a success in meeting all objectives and supports the decision to move forward with Phase 2 to obtain vertical core samples from the entire depth of a SST haunch, sidewall, and footing scheduled for initiation in March 2014. In conjunction with the coring effort, WRPS intends to perform non-destructive evaluation techniques to the tank dome haunch above the sidewall. The NDE methods will likely alternatives to coring assumed leaker SSTs in the future.

SI-4 Completed FY 2010 and FY 2011 Visual Inspections

The criteria provided to tank farm inspectors for the examination of the reinforced concrete dome include the identification of concrete spalling, rust stains, cracks $\geq 1/16$ -in wide, and visible reinforcing steel patterns. All of these indications would suggest a certain level of degradation of the concrete dome. A primary focus of the inspections was the tank haunch section of the concrete dome where extensive cracking would suggest too high of a demand on the reinforced dome in its current condition.

Where possible, images from current in-tank inspections were compared to historical images of the same region. A photo comparison of 241-B-102 is provided in Figure 7. Visual inspection of Tank 241-B-102 and all other tanks inspected in FY 2010 and FY2011 did not reveal any degradation of the concrete dome and haunch.



Figure 7. Comparative Photographs of Tank 241-B-102 Haunch Region

Tanks inspected FY 2010:

Tanks inspected in Fiscal Year (FY) 2010 include SSTs 241-A-105, 241-A-106, 241-AX-102, 241-B-102, 241-BY-110, 241-C-110, 241-S-101, 241-S-103, 241-S-104, 241-S-108, 241-SX-101, and 241-U-104. Results of the inspections showed no detectable change in the concrete dome condition from previous inspections. No areas of concern were noted in any of the FY 2010 inspected SST reinforced concrete domes.

Tanks inspected FY 2011:

Tanks inspected in Fiscal Year (FY) 2011 include SSTs 241-AX-101, AX-103, T-112, C-112, B-106, AX-104, T-102, TX-101, TX-104, U-106, C-101, SX-107. Results of the inspections showed no detectable change in the concrete dome condition from previous inspections. No areas of concern were noted in any of the FY 2011 inspected SST reinforced concrete domes.

It was originally planned to continue SST visual inspections at a rate of 12 per year, but funding shortfalls temporarily suspended this effort for FY 2012.

Tanks inspected FY 2013:

Tanks inspected in Fiscal Year (FY) 2011 include SSTs 241-A-103, BX-101, BX-103, BX-110, BY-101, BY-102, BY-111, S-109, S-111, SX-106, TX-112, U-111, B-203, B-204, T-111, T-203, T-204, TY-105. The report for the inspection of these tanks is currently being developed. Preliminary review has shown no signs of structural distress.

SI-5 Test Dome Concrete and Rebar 'Plugs'

A 55-inch diameter section of reinforced concrete (RC) was removed from the dome of C-107 in December 2010 [7]. The RC section was removed completely intact, double wrapped in plastic, and placed in an isolated area in 241-C farm. Figure 8 displays the unwrapped, intact 55-inch section of RC removed from 241-C-107.



Figure 8. SST 241-C-107 Dome Plug

The plug was inspected in the field [8]. During the inspection the following actions were taken:

- Measure full depth of 'Plug'
- Measure depth to top mat of rebar
- Measure depth to bottom mat of rebar
- Photograph 'Plug', cracks, voids, rebar, and aggregate

The field inspection revealed that the concrete was in good condition, with no noticeable cracks or voids. The placement of the rebar generally matched the design drawings, with the benefit of slightly more concrete cover than designed.

A total of fourteen nominally 4.2" diameter cores were removed from the plug and sent to CTL Group in Skokie, IL for testing. Of the 14, 12 cores were underwent mechanics testing and 2 were set aside for Petrographic examination.

Prior to mechanics testing, the following inspection was performed on the concrete cores:

- Measure diameter and length
- Measure any cracks
- Measure any voids
- Photograph the core, cracks, voids, rebar (if any), aggregate

The core inspections revealed that minimal cracking was present and only minor voids present.

The 12 cores subjected to physical testing underwent tests for the following:

- Transverse Natural Frequency ASTM C215 [11]
- Modulus of Elasticity – ASTM C469 [12]
- Poisson's Ratio – ASTM C469
- Compressive Strength – ASTM C39 [13]

Results of the physical testing of the C-107 concrete cores are presented in Table II.

TABLE II. SST 241-C-107 Concrete Core Physical Test Results Summary

Core Number	Average Transverse Frequency (Hz)	Dynamic Modulus (ksi)	Elastic Modulus (ksi)	Poisson Ratio	Compressive Strength (psi)
C-107#1	6493	6700	5900	0.20	9890
C-107#2	6527	6900	6500	0.23	9670
C-107#3	6480	6800	6000	0.24	9290
C-107#5	6447	6700	5950	0.24	8530
C-107#6	6443	6900	6000	0.23	9030
C-107#11	6253	6300	5850	0.23	6810
C-107#12	6373	6500	5800	0.21	5890
C-107#13	6313	6400	5750	0.23	6800
C-107#15	6343	6600	5900	0.23	7530
C-107#17	6480	6700	6100	0.19	7800
C-107#19	6320	6400	5550	0.20	6840
C-107#20	6393	6600	5950	0.20	8850

From the values presented in Table 2, the compressive strength averaged 8000-psi, which is more than 2.5 times the design strength of 3000-psi. The modulus of elasticity and Poisson ratio are in agreement with the higher strength concrete.

Based on the results of petrographic examination [12], the concrete represented by the 2 cores is in good condition. No distress (cracking or excessive micro-cracking) is observed in either core.

The concrete does not show any evidence of chemical attack, significant alkali-aggregate reactions, or other deleterious mechanisms involving aggregates and/or hydrated cement.

The concrete in both cores exhibits good physical paste properties. Apart from localized softer paste at the immediate top surface, the paste in the cores is hard and dense through the depth of the concrete. Distribution of aggregates and other paste constituents is uniform. Macroscopically, the cores are well consolidated (no large voids). Additionally, the depth of carbonation for the cores was shallow, approximately 0.04 to 0.08 in. (1 to 2 mm) from the top surface.

The removal, inspection and testing of the rebar removed from the SST 241-C-107 dome 'plug' was performed in early 2013. Twenty pieces of rebar were shipped to CTL Group for inspection and testing. Visual inspection of the rebar was successfully performed at CTL Group. The inspection indicated that the rebar removed from the 'Plug' is in good condition, with no cracks or defects.

The C-107 rebar were segregated based on length. The five specimens 28 inches or longer were subjected to ASTM A615 [15] testing and not modified prior to testing. With the exception of Sample 44, specimens less than 28 inches long were cut, machined, and reduced to the size required for ASTM A370 [16] testing.

Forty-eight specimens were loaded in the calibrated test frame in accordance with test procedures described in ASTM A370. The test data provided included yield and tensile strengths, modulus of elasticity, and percent elongation. The yield strength was determined using the 0.2% Offset Method, in accordance with ASTM A370. An example of an ASTM A370 test specimen is shown in Figure 8. Results of A370 tension testing are presented in Table III.



Figure 9. C-107 ASTM A370 Specimen

Table III. C-107 Rebar ASTM A370 Tension and Hardness Test Results

CTLSample ID	Yield Strength (ksi)	Tensile Strength (ksi)	Elongation (%)	Modulus of Elasticity (ksi x 1000)
37-1a	50.50	83.50	28.00	34.00
37-1b	51.50	84.00	30.00	32.50
37-2a	47.70	78.50	33.00	28.50
37-2b	44.60	78.50	33.00	30.30
37-2c	46.80	78.00	33.00	27.50
39-1	49.40	79.00	32.00	32.70
39-2a	47.30	76.50	32.00	29.70
39-2b	44.70	76.00	32.00	29.80
39-2c	46.00	76.50	34.00	14.50*
39-2d	47.70	76.50	33.00	25.10
39-2e	47.20	76.00	32.00	28.60
40a	45.20	76.00	31.00	27.30
40b	43.90	77.00	33.00	28.80
40c	43.50	77.00	33.00	35.80
40d	42.10	77.50	31.00	27.70
40e	43.70	78.00	31.00	27.10
41-1	48.70	83.00	30.00	31.30
41-2	47.80	79.50	30.00	25.70
41-3a	48.30	76.50	30.00	29.60
41-3b	45.60	77.00	32.00	32.30
41-3c	47.90	77.00	32.00	26.60
41-3d	48.60	77.00	31.00	28.30
41-3e	48.00	77.00	33.00	28.10
41-4a	49.40	80.00	33.00	30.30
41-4b	48.50	79.50	33.00	27.30
41-4c	45.10	79.00	33.00	28.00
41-4d	49.60	80.00	34.00	28.70
41-4e	46.50	80.50	33.00	32.30
41-4f	47.00	79.50	33.00	28.00
42a	51.00	80.50	33.00	28.10
42b	47.80	80.50	29.00	29.10
42c	46.40	78.50	32.00	30.00
42d	44.60	78.00	33.00	33.20
43-1a	44.00	76.00	31.00	28.50
43-1b	46.70	77.00	32.00	31.20
43-2a	45.70	80.00	32.00	29.90
43-2b	48.70	80.00	32.00	28.80
43-2c	47.70	80.50	32.00	31.60
43-2d	47.20	80.50	32.00	29.10
43-2e	45.90	79.50	32.00	25.10

*Low modulus attributed to misplacement of extensometer

Table III (cont'd). C-107 Rebar ASTM A370 Tension Test Results

CTLSample ID	Yield Strength (ksi)	Tensile Strength (ksi)	Elongation (%)	Modulus of Elasticity (ksi x 1000)
43-3a	49.00	84.50	30.00	27.60
43-3b	48.90	84.00	32.00	26.20
43-3c	48.90	84.00	32.00	26.90
43-3d	47.70	83.50	31.00	31.60
43-3e	51.50	83.50	30.00	30.30
45a	46.00	77.00	32.00	30.50
45b	44.80	77.50	32.00	26.40
45c	47.90	77.00	32.00	26.30
AVERAGE	47.15	79.08	31.85	28.89

Five rebar pieces were 28 inches or longer, as received. These rebar samples were tension tested as full rebar sections, in accordance with ASTM A615. An 8 inch gauge length with 2 inch gauge marks was provided between the load frame grips. An example of the rebar test specimen prepared for testing is provided in Figure 10. The results of the tension tests on the full section rebar are provided in Table IV



Figure 10. C-107 ASTM A615 Tension Test Specimens

Table IV. C-107 Rebar ASTM A615 Tension Test Results

CTLSample ID	Yield Strength (ksi)	Tensile Strength (ksi)	Elongation (%)
37-3	46.4	65.0	5.6
37-4	49.5	76.0	19
38	47.3	74.0	15
39-3	46.4	73.5	18
39-4	50.9	75.5	24
AVERAGE	48.1	72.8	16.3

Including A370 and A615 test results, the average yield strength of all the C-107 rebar is 47.24-ksi. This value is greater than the 40-ksi yield strength for the Grade 40 rebar specified in the original tank construction and therefore greater than the value used in the Analysis of Record. This is expected as the 40-ksi yield strength is a minimum value with nominal values typically higher

SI-6 Develop Engineering Mechanics Document

The engineering mechanics document will be prepared and maintained by WRPS to contain the current best understanding of engineering mechanics properties of each tank. The mechanics document will contain information on concrete and rebar properties related to those use in the structural analyses and those determined from Non-destructive Testing and physical testing.

SST Structural Integrity Summary

Results from the completed tasks related to structural integrity have been favorable. The structural analyses of record for the Type II and Type III SSTs indicate that the tanks are structurally sound. Available SST dome surveys show that dome deflection is not a concern, based on the current loads on the tanks. The demonstration of SST sidewall coring successfully proved that actual tank coring can be performed. The real objective, yet to be performed, is to obtain actual concrete cores from the sidewall of SST 241-A-106. The completed visual inspections do not reveal any signs of concrete degradation in the dome and haunch regions of the associated SSTs. Actual test results from concrete cores and rebar removed from the dome of SST 241-C-107 show that the concrete and rebar is in good condition and has higher strength than considered in the analytical models.

REFERENCES

1. RPP-RPT-43116, *Expert Panel Report for Hanford Single-Shell Tank Integrity*. 2009, Washington River Protection Solutions, Washington.
2. RPP-46442, Rev. 0, *Single-Shell Tank Structural Evaluation Criteria*. 2010, Washington River Protection Solutions, Richland, Washington.
3. RPP-RPT-49989, Rev. 0, *Single-Shell Tank Integrity Project Analysis of Record: Hanford Type II Single-Shell Tank Thermal and Operating Loads and Seismic Analysis*. 2011, Washington River Protection Solutions, Richland, Washington.
4. RPP-RPT-49990, Rev. 0, *Single-Shell Tank Integrity Project Analysis of Record: Hanford Type III Single-Shell Tank Thermal and Operating Loads and Seismic Analysis*. 2011. Washington River Protection Solutions, Richland, Washington.
5. RPP-26516, Rev. 1, *SST Dome Survey Program*. 2013, Washington River Protection Solutions, Richland, Washington.
6. RPP-PLAN-47370, Rev. 2, *Sidewall Core Drilling Plan for the Single-Shell Tank 241-A-106 Sidewall Coring Project*. 2013, Washington River Protection Solutions, Richland, Washington.
7. RPP-PLAN-48753, Rev. 0, *Analytical Test Plan for the Removed 241-C-107 Dome Concrete and Rebar*. 2011, Washington River Protection Solutions, Richland, Washington.
8. RPP-RPT-50934, *Inspection and Test Report for the Removed 241-C-107 Dome Concrete*. 2012, Washington River Protection Solutions, Richland, Washington.
9. RPP-RPT-55202, *Dome Survey Report for Hanford Single-Shell Tanks*. 2013, Washington River Protection Solutions, Richland, Washington.
10. RPP-RPT-54564, *Inspection and Test Report for the Removed 241-C-107 Dome Rebar*. 2013, Washington River Protection Solutions, Richland, Washington.
11. ASTM C 215-08, *Standard Test Method for Fundamental Transverse, Longitudinal, and Torsional Frequencies of Concrete Specimen.*, 2008, ASTM International, West Conshohocken, PA.
12. ASTM C 469-02, *Standard Test Method for Static Modulus of Elasticity and Poisson's Ratio of Concrete in Compression*. 2002, ASTM International, West Conshohocken, PA.
13. ASTM C 39-05, *Standard Test Method for Compressive Strength of Cylindrical Concrete Specimen*, 2005, ASTM International, West Conshohocken, PA.

14. ASTM C 856-04, *Standard Practice for Petrographic Examination of Hardened Concrete*. 2004, ASTM International, West Conshohocken, PA.
15. ASTM A370-12a, *Standard Test Methods and Definitions for Mechanical Testing of Steel Products*, American Society for Testing and Materials International, West Conshohocken, Pennsylvania.
16. ASTM 615-12, *Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement*, American Society for Testing and Materials International, West Conshohocken, Pennsylvania.