

West Valley Demonstration Project Guide to Successful Waste Shipments

Session 99

Daniel Sullivan
Facility Project Director

Department of Energy – West Valley

March 8, 2017

Two Successful Projects



High-Level Waste Canister Relocation and Storage Project



Vitrification Component Shipment



HLW Canister Relocation and Storage Project

Main Plant Process Building Cask Rail Cart Canister decon, loading and Overpack welding occur inside Main Plant **HLW Cask Storage Pad** Forester station Room and Apron ermon Chemical Photograp Coll Automatic Welding System Haul Path ~ 2,600 feet Air Pallets used to move casks into and within. Load-In Facility TL220 operates along 'runway" in Load-In Facility **HLW** and Equipment Decontamination Room Security checkpoint Relocation North Parking Lot **Project** Vertical Cask Impacted Areas and Flow Path ransporter and tugger move casks on outdoor roadways

Vertical Storage Cask Fabrication/Staging area




Success Story

- High-Level Waste crews completed the relocation and long term interim storage of 275 canisters of vitrified HLW one year ahead of schedule.
- All work completed safely and compliantly.



Final Cask Transported to Interim Storage Pad

Approved for Public Release; Further Dissemination Unlimited





OFFICE OF ENVIRONMENTAL MANAGEMENT

Vitrification Component – Shipment Project



Approved for Public Release: Further Dissemination Unlimited

Vitrification Melter

Packaged: 14'x13'x13', 195 tons

CFMT (Concentrator Feed Make-up Tank)

Packaged: 13'x14'x19', 167 tons

MFHT (Melter Feed Hold Tank) Packaged: 13'x14'x16', 150 tons CHBWV received Special Package Authorization from the US Nuclear Regulatory Commission (NRC) to ship the melter, primarily by rail, for disposal to Waste Control Specialist (WCS) in Andrews, Texas in October FY17.

Contract Awards





Impact Limiter Installed on Melter Package

- Shipment of Vitrification Melter, Concentrator Feed Makeup Tank (CFMT) and Melter Feed Hold Tank (MFHT)
 - MHF Logistics (MHF), Waste Control Specialists (WCS) and CHBWV walk-down site upgrades and measure melter package with impact limiter installed – mid-September
 - MHF begins mobilization onsite and assembles equipment late October
 - MHF begins loading three heavy, low-level waste packages onto heavy haul trailers for transport to Blasdell, NY (35 miles north of the site)
 - Low-level waste packages loaded on a Special Railcar for transport to WCS in Andrews, Texas for permanent disposal – mid-November

OFFICE OF ENVIRONMENTAL MANAGEMENT

On-Site Preparations for Transport





Gantry Crane Assembly



Journey Begins



After more than a decade, the vitrification components were transported by heavy haul truck from the site to the rail yard in Blasdell, New York.



Each component was transferred to an 8-axle rail car, separated by idlers and locomotives — approximately 650 feet long.

Permanent Disposal



Careful & meticulous coordination of Team

+

Advanced planning

+

Rigorous safety focus

=

On schedule execution

First Time DOE Shipped for Disposal a Waste Package that has Undergone a WIR Evaluation and Determination Process.



Melter, CFMT, and MFHT Grouted in Place at WCS

Approved for Public Release; Further Dissemination Unlimited

- A highly visible waste shipment traveling 35 miles through neighborhoods, highways, **Tribal Territory**
- 144 wheels, police escorts, utility companies, traveling at less than 30 miles per hour, placarded "Radioactive" (Class 7)
- Loaded onto a Special Train (Three 8-axle rail cars, each separated by idlers and locomotives – approximately 650 feet long) traveling across 10 states

Why no media attention, 911 calls, public interest or concerns?

Timely, open, transparent, frequent, consistent communication to a variety of

stakeholders – start to finish.



with Congressman Tom Reed

Communication

- Coordinated Communication Plan (DOE-EM 31, 33, Contractors, Agencies)
- Prepared Fact Sheet
- Communication with the public, DOT, DOE, New York State Energy Research and Development Authority (NYSERDA), NRC, Seneca Nation, local, state and federal elected officials, regulatory agencies, New York State Department of Environmental Conservation, Coalition for West Valley, Emergency Responders, members of the Citizen Task Force and the media
- Emergency Response Plan, including an on-site exercise involving local responders
- Single Point of Contact for Inquiries



A site-wide emergency and evacuation exercise provided opportunity to test the response capabilities of numerous on and off-site response teams.

ONE TEAM

- Safety inspections of heavy haul transportation equipment (trucks, rail cars, equipment used to transload components)
- 24-Hour Emergency Response Contact List
- Both heavy haul truck and rail cars equipped with tracking capabilities for monitoring during transport
- Experienced Transload Contractor (MHF)
- Experienced Transporter (Perkins)
- 27 total permits required to move from West Valley to transload rail station located 35 miles north of the site
- 12 Third-party contractors supported the move

LOGISTICS AND PLANNING

- Transportation planned in accordance with all relevant regulations, including those of the DOE, DOT, NRC, as well as applicable state, local and tribal requirements
- Shipments designed to comply with all fee and permit/clearance requirements



SUCCESS SUMMARY

- ONE TEAM
- LOGISTICS AND PLANNING
- EXPERIENCED CONTRACTORS
- EFFECTIVE COMMUNICATIONS